

# Commissioning Qualifications and Submittal Requirements 2024 Boulder Energy Code Commercial Provisions

#### **SCOPE**

The 2024 City of Boulder Energy Conservation Code (CoBECC) contains separate provisions for *commercial buildings* and *residential buildings*. This policy outlines *approved agency* qualification requirements for systems commissioning in accordance with C408, and the commissioning letter needed to demonstrate compliance with the 2024 Boulder Energy Code *commercial provisions*.

#### **APPLICABILITY**

The 2024 Boulder Energy Code addresses the design of an energy-efficient building envelope (consisting of the roof and ceiling, walls, floors, and foundation assemblies that surround the conditioned space) as well as the selection and installation of energy-efficient mechanical, lighting, and service water-heating systems.

The *commercial provisions* of the 2024 Boulder Energy Code apply to new buildings with conditioned space that are not defined as *Residential Buildings* (see definition below) and any such buildings undergoing an addition, remodel, alteration, repair, change of occupancy that would result in an increase in demand for either fossil fuel or electrical energy, or change of use.

The residential provisions of the 2024 Boulder Energy Code apply to residential buildings, defined as: Residential Buildings are detached one- and two-family dwellings and multiple single-family dwellings (townhouses) and Group R-3 and R-4 buildings three stories or less in height above grade plane.

### **SECTION A. QUALIFICATION REQUIREMENTS**

#### **Systems Commissioning Qualifications**

Commissioning Professional (CCP) or equivalent.

An <i>approved agency</i> responsible for the execution of the commiss	sioning process must have at least
one of the following qualifications:	
☐ A building commissioning certification from an ISO/IEC 17	'024-accredited agency or another
entity that certifies building commissioning professionals;	or

## **SECTION B. SUBMITTAL REQUIREMENTS**

☐ Staff credentials recognized by the Building Commissioning Association, such as the Certified

If system commissioning is required in accordance with Section C408, submit a letter during construction drawing plan review that includes the information below. The review may not be approved without this letter.

and/or system commissioning	rov	red without this letter.
□ Name of the individual (if known) and/or company that will perform the envelope verifiand/or system commissioning		Project address and log number
and/or system commissioning		General contractor's name
. ,		Name of the individual (if known) and/or company that will perform the envelope verification
☐ Describe whether the commissioning agent is a registered design professional or an app		and/or system commissioning
		Describe whether the commissioning agent is a registered design professional or an approved

agency. Letters for design professionals must provide their specialty and license number. The
design professional stamping the design cannot be same design professional performing the
commissioning but can be in the same firm. Letters for approved agencies must indicate which
of the qualification requirements are met to qualify them as an approved agency.
For phased construction projects, identify the phase or phases when commissioning will occur at a level of completion expected to satisfy the requirements of the Preliminary
Commissioning Report.
The letter must be signed and dated by the project developer, owner, or authorized agent.

# 2024 Boulder Energy Code - Commercial



2024 City of Boulder Energy Conservation Code

Applies to: All New Buildings, Additions, Alterations and Repairs which require a permit from the City.

Exception: Mechanical systems in buildings where the total mechanical equipment capacity is less than 480,000 Btu/h (140,690 W) cooling capacity and 600,000 Btu/h (175,860 W) heating capacity.

#### \*Supporting documentation as required for energy code compliance.

- Air Leakage Testing Form and Report,
- Preliminary Commissioning Report (including issues log),
- Functional Testina Documentation, Lighting Controls

	- Functional Testing Documentation, Lighting Controls - Functional Testing Documentation, Mechanical and Service Water Heating Systems
Project Information	Project Name:
	Project Address:
	Commissioning agent, agency or authority that completed the commissioning work:
Air Leakage Testing*	The completed bulding was tested and the air leakage rate of the building envelope does not exceed 0.25 cfm/ft2 at 0.3" water gauge: (owner representative to initial here)
Commissioning Plan	Commissioning Plan was used during construction and includes all items : (owner representative to initial here)
Systems Adjusting and Balancing*	Systems Adjusting and Balancing has been completed. Air and water flow rates have been measured and adjusted to deliver final flow rates within the tolerances provided in the product specifications.
	HVAC Equipment Functional Testing has been executed. If applicable, deferred and/or follow-up testing is scheduled to be provided on: (date)
Functional Testing*	HVAC Controls Functional Testing has been executed. If applicable, deferred and/or follow-up testing is scheduled to be provided on: (date)
	Economizer Functional Testing has been executed. If applicable, deferred and/or follow-up testing is scheduled to be provided on: (date)
	Receptacle and Lighting Controls Functional Testing has been executed. If applicable, deferred and/or follow-up testing is scheduled to be provided on: (date)
	Service Water Heating System Functional Testing has been executed. If applicable, deferred and/or follow up testing isscheduled to be provided on: (date)
Supporting Documents	Manuals, record documents and training have been completed or are scheduled.  • System documentation has been provided to the owner or scheduled to be delivered to the owner on: (date)  • Record documents have been submitted to owner or scheduled to be delivered to the owner on: (date)  • Training has been completed or scheduled to be completed on: (date)
Preliminary Commissioning Report*	Preliminary Commissioning Report submitted to Owner and includes all items required: (owner representative to initial here)
Certification	I hereby certify that the commissioning provider has provided me with evidence of mechanical, service water heating and lighting systems commissioning in accordance with the 2020 City of Boulder Energy Conservation Code.  Signature of Building Owner or Owner's Representative   Date